



SAINT-GOBAIN CONSTRUCTION PRODUCTS SA (PTY) LTD

ABE - GENERAL CONSTRUCTION





Item No		Amount
------------	--	--------

	<u>BILL NO. []</u>	
	<u>PRELIMINARIES</u>	

Bill No. 1 Preliminaries		
-----------------------------	--	--

Carried to Summary	R	<u>Not Priced</u>
--------------------	---	-------------------



Item No		Quantity	Rate	Amount
	<u>BILL NO. []</u>			
	<u>a.b.e GENERAL CONSTRUCTION</u>			
	<u>NOTE:</u> All products to be applied according to a.b.e. instructions - all relevant data sheets to be read for mixing instructions, pot life, overcoating times etc.			
	<u>GROUTING</u>			
	<u>"ABE DURAGROUT" - Non-shrink grout</u>			
	"abe duragrout" Non-shrink grout bedding under base plates.			
1	Bedding approximately 12mm thick under 180 x 180mm base plate including chamfered edges all round.	No		Not Priced
2	Bedding approximately 25mm thick under 180 x 180mm base plate including chamfered edges all round.	No		Not Priced
3	Bedding approximately 20mm thick between 300 x 300mm steel base plate and stub column, and chamfered all round.	No		Not Priced
	<u>EPOXY GROUTING OF STEEL BARS</u>			
	<u>"ABE EPIDERMIX 395" - liquid epoxy grouting OR "ABE EPIDERMIX 396" - paste epoxy grouting.</u>			
	"abe epidermix 395" - liquid OR "abe epidermix 396" - paste, epoxy grouting of steel reinforcing rods.			
4	16mm dia. Steel rods into 32mm dia. Holes 250mm deep	No		Not Priced
	<u>FIXING GLASS BALUSTRADES</u>			
	<u>"ABE DURAGROUT " - non-shrink grout</u>			
	"abe duragrout " non-shrink grout applied to prepared areas.			
5	To both sides of bottom edge of 12mm glass balustrade, (elsewhere), 67mm deep in 45mm wide recess in top of concrete on neoprene setting blocks and	m		Not Priced
	Carried to Summary		R	Not Priced
	Bill No. 2			
	General Construction (abe)			



FINAL SUMMARY				Amount
Bill No		Page No		
1	Preliminaries	2		Not Priced
2	General Construction (abe)	3		Not Priced
Carried to Form of Tender			R	Not Priced